The wood to be stacked by the contractor in the portions approved by the Executive Engineer or his representatives.

Stacks must be rectangular shape. The sides being vertical and straight and the tops level: the wood must be laid evenly straight and close, the pieces composing the walls must be laid at right angle to the direction of such walls, having first been sawn to an uniform length as above. The interior of the stacks must be packed as closely as possible, the pieces being regularly laid with their lengths all in the one direction, which leave no vacant space.

The stacks to be built of such dimensions that the cubical measurements of each is a multiple of 68 cubic feet.

17 feet by 8 feet by 5 feet = 680 cubic feet 10 tons.

Sixty-eight feet of closely stacked wood will be accepted as equivalent to one ton.

The Executive Engineer or his representatives will inspect the wood as it is being stacked and shall have power to reject any pieces that are hollow, rotten crooked or otherwise unsuitable for fuel for engine, he will also satisfy himself that the pieces are in accordance with the dimensions specified above, and that the stacks are built as required. He shall also have power to reject any stacks which do not, in all respects, comply with the terms of this specification.

The wood must be at the risk of the contractor until it is stacked, approved, measured and accepted by the Executive Engineer or his representatives.

When stacks are taken over, the contractor or his representative must be present during the measurement and must sign the record of measurement made by the Executive Engineer or his representatives in token of his agreement to the corrections thereof.

K. SRINIVAS IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Dated 16th October 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 4th November 1911, for restoring the breached Akkur anikat and tank Registered No. 125, Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the breached Akkur anikat and tank Registered No. 125, Channapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Item No.	*Items of work*	*Per*	*Quantity*
Bund—			
1	Earthwork	C. yd.	16,023
2	Foundation for revetment and grip ...	„	1,149
3	Old stone pitching (1' thick) ...	S. yds.	2,564
4	New stone pitching (1' thick) ...	„	6,180
5	Turfing slope	„	10,391
6	New grade stones ...	Each	51
7	Index stones	„	51
8	Register No. stone	„	1
9	Bench mark stones	„	2
10	Gauge stones	„	1
11	Date stone	„	1

	Items of work.	Per	Quantity.
Waste weir—			
1	Dismantling coping slab	L. S.	
2	Brick in chunam	C. ft.	119
3	Plastering with chunam	Sqr.	7·28
4	Repairs to old stone work	L. S.	
5	Repairing and replacing coping slab ...	S. ft.	150
6	Fitting with joggles	Each	17
Sluice—			
1	Cutting bund and examining No. 1 and 2 sluices, including repairing ...	L. S.	
Anikat—			
1	Excavating and removing sand ...	C. yd.	215
2	Dismantling apron	"	95
3	Excavating foundation in clay and soft rocky soil	"	463
4	Baling water	L. S.	
5	Dismantling concrete	C. ft.	1,017
6	Concrete filling	"	1,691
7	Burnt stone in chunam	"	9,519
8	Burnt brick in surki mortar... ...	"	1,210
9	Burnt stone in chunam with top surface dressed	"	2,286
10	Burnt stone slabs ...	S. ft.	1,338
11	Joggles	"	110
12	Plastering with surki mortar ...	Sqr.	21·05
13	Pointing with cement	"	15·04
14	Repairs to old foundation at existing face where needed by underpinning ...	L. S.	
15	Unforeseen charges	"	
16	Resetting old stone apron ...	C. yd.	152
17	Rough stone work, new ...	"	248
18	Providing new teakwood shutter to scouring sluice ...	L. S.	
19	Providing new teakwood shutter for head sluice with iron rod etc., complete.	"	
20	Earth filling to breach	C. yd.	208
21	Inserting bond stones to cracks ...	L. S.	
22	Grouting front apron	Sqr.	11·16

V. R. NIJAGAL,
Executive Engineer.

MYSORE GOVERNMENT STATIONERY DEPOT.

TENDERS FOR THE SUPPLY OF WRITING, PRINTING AND OTHER PAPERS.

Notice dated 18th October 1911.

Sealed tenders for the supply of Writing, Printing and other Papers, required for the Government of Mysore, during the official year 1912-13, will be received by the Superintendent of Stationery, Mysore Government, at his office at Bangalore, up to 5 P.M. on Saturday the 6th January 1912.

2. Tenders should be superscribed "Tender for the supply of Writing, Printing and other Papers," and should be accompanied by samples and by a deposit of Rs. 500 as earnest money, which will be returned after the disposal of tender, to all unsuccessful tenderers, and be liable to be forfeited if the successful tenderer or tenderers fail to fulfil the conditions of his or their contract. Bank cheques or Government of India Pro-notes endorsed in the name of Superintendent of Stationery, Mysore Government, are preferred.

3. Samples of the required papers used by the Government of Mysore can be seen at the Stationery Depot, Mysore Government, Bangalore, any day except Sundays and holidays, between the hours of 11 A.M. and 4 P.M.

4. The successful tenderer or tenderers will be required to execute a security bond as per specimen to be seen in the office, on 8 annas Mysore Government Stamp paper and to deposit a security of five per cent on the value of papers for which the tender is accepted, for the due fulfilment of his or their contract.

5. The quantities specified in the schedule annexed hereunder are only *probable requirements*, which the Mysore Government are not bound to purchase in full from the contractors, who must be prepared to make periodical deliveries of papers, only on receipt of distinct orders from the Superintendent of Stationery, from time to time, complete delivery of the first order being made by the end of April 1912. It shall be in the discretion of the Superintendent to extend the time for such delivery, on reasonable cause being shown. All supplies will be subject to examination by the Superintendent of Stationery. Papers not considered up to quality and sample will be rejected and will remain at the risk of the contractors. *All papers must be entirely free from mechanical wood.*